



**CITY OF ROCKLAND**  
Request for Proposal  
**RPCF Primary Clarifiers Coating**

**Submission Deadline: Tuesday, March 4, 2025, no later than 2 pm**

Questions will be submitted/answered only by e-mail.  
All answers to all questions will be available upon request.

RFP Contact Name:	Yarona Orta-Vidal, PhD Assistant Director & Env. Compliance Manager Rockland Pollution Control Facility
Telephone Number:	207-596-0224 ext. 2
Email Address:	yortav@ldhrocklandmaine.gov

**INTRODUCTION**

The City of Rockland invites and welcomes proposals to coat two Primary Clarifiers. Please take the time to carefully read and become familiar with the proposal requirements. All proposals submitted for consideration must be received by the time as specified under the "SUBMISSION DEADLINE."

**PROJECT AND LOCATION**

The proposal is being requested for the coating of two RPCF's Primary Clarifiers. The location is at the Rockland Pollution Control Facility at 40 Tilson Ave., Rockland, ME.

**PROJECT COMPLETION DATE**

- Project shall be completed by June 13, 2025.

**DESCRIPTION OF WORK:**

1. **Specs:**
  - a. Prepare surfaces. Power wash the interior concrete walls, floor, and all steel work to remove all loose and falling rust paint and dirt.
  - b. Power jet blast the steel to an SP10. In blasting the rake arm, center wall, center wall components, scum trough, underneath the walkway/bridge, and any ferrous metal parts.
  - c. Coat surfaces. Apply at least two coats of 99 Star Tar to the steel at 6-8 mils all per coat.
  - d. Clean-up during and after project is completed.
2. Two primary clarifiers
3. Diameter: 45 ft. each
4. Inner diameter center columns - 1'-11"
5. Large diameter drains (don't go all the way to the floor) 12" D, #18
6. Double bridge
7. The rake is about 5' from the bottom and it is approximately 7' tall.
8. Both clarifiers are covered.